

QUOTATION

Sub: Providing of UPS wiring, UPS switch boards at Aaravali Guest House Corridor for Internet / Wifi purpose and providing fan points at Himachal Guest House Corridor at NIRDPR.

NIRD&PR is an organization of the Ministry of Rural development and Panchayati Raj, Govt. of India located at Rajendranagar, Hyderabad 500030. We request you to quote for the above mentioned work for the following items. The downloaded Quotations should be filled and sealed, submitted to under signed on or before **07.11.2022** at 3.30 PM the same will be opened on the same day in front of bidders.

S.No	Description of items	Qty	Per	Rate	Amount
1.	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.				
1.1.	Group C	20	Pts		
2.	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.				
2.1.	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	160	Mtrs.		
3.	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 2 nos. 3 pin 5/6 A modular socket outlet and 2 nos. 5/6 A modular switch, connections etc. as required. (For light plugs to be used in non residential buildings).	20	Nos.		
4.	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. as required.	20	Nos.		

5.	Supplying and fixing of Anchor bolts of 16mm dia for fixing of existing ceiling fans, etc, complete as required.	20	Nos.		
				Total Rs.	

(Rupees

only)

Terms & Conditions:

1. The rates quoted should be inclusive of all taxes
2. Material suppliers confirmed ISI standard.
3. The material should be supplied at the site as directed by the Executive-in-charge in good condition and nothing extra will be paid for transportation.
4. Duration of completion of period 30 days.
5. Tenderer should inspect the site before quoting the price.
6. ITL for display in Web site.

Yours faithfully
For on behalf of Director General

Executive Engineer

4/11/22