



राष्ट्रीय ग्रामीण विकास एवं पंचायती राज संस्थान

(ग्रामीण विकास मंत्रालय, भारत सरकार)

राजेन्द्रनगर, हैदराबाद - 500 030 (भारत)

NATIONAL INSTITUTE OF RURAL DEVELOPMENT & PANCHAYATI RAJ

(Ministry of Rural Development, Government of India)

Rajendranagar, Hyderabad - 500 030 (India)

NO. EE/CMU/16-17/311 (P.F Dec 2016)

Dt. April 18, 2017.

P.V. DAYANAND
EXECUTIVE ENGINEER

NIQ No: EE/NIRD/17-18/NIQ/1

Sub:- Repairs of Ducting work and shifting of Air Conditioning Unit indoor and out door unit of 8.5 TR capacity at Auditorium with required material etc., complete.

NIRD is an organization of the ministry of Rural Development, Government of India located at Rajendranagar, Hyderabad 500 030. We are interested to ^{replace} work of 1 No: 8.5 TR capacity A/C should be brought in to good working condition with full load. The works required are indicated below. Hence Quotations should be sealed and submitted to undersigned on or before 27.04.2017 by 3.00pm, Quotations will be opened at 3:30 pm on the same day in the presence of the prospective bidders who are present.

S.No	Description	Qty	Rate (in words)	Amount
1.	Supply and fixing of GI duct for supply air of the following size fabricated from 24 guage sheet bending into rectangular box including necessary fixing material like power plugs suitable size screws and coup washers of size 42" x 18" x 8rmt approx cladding sheet for return and supply duct including closing of the walls opening	1		
2.	Supply and fixing of GI duct for the following size fabricated from 24 guage sheet bending into plenum box for fixing of air handling unit on the terrace including necessary fixing material like power plugs suitable size screws and coup washers and fabricated angular stand for placing AHU in the box with connection of the duct 8" x 6' x 5" = 264 sqfts including of wastage of 10%	1		
3.	Supply and fixing of thermo coal sheet for the duct of supply air and return air and plenum box above the duct and cladding with the aluminium sheet for the safety of the duct to the atmosphere conditions including labour and handling charges	1		
4.	Supply and fixing of nital rubber for the duct of supply and return air inside the rectangular duct and the plenum box for placing the air handling unit with solution for pasting including labour and handling charges	1		

फोन : 24008526, तार : ग्राविक, फैक्स : 91-040-24016500 / 24015277, ई-मेल : cit@nird.gov.in, nirdhy@hub.nic.in

Phone : 24008526, Grams : Gravik, Fax : 91-040-24016500 / 24015277, E-mail : cit@nird.gov.in, nirdhy@hub.nic.in

We care for the environment

5.	Supply and fixing of canvas connection for the AHU of the duct to connect the main supply duct including material like power plugs suitable size screws and coup washers with labour and handling charges	1		
6.	Dismantling of indoor unit AHU and fixing on the roof top with dismantling of outdoor unit and shifting from one place to another with required essential material.	1		
7.	Interconnection of copper pipe for suction and discharge line with brazing the piping and nitrogen pressure testing of the system and leakage arresting of the system.	1		
8.	Dehydration, pressure testing, vaccumisation the system and refilling of gas f-22 with standard procedure and commissioning of the system with required labour and handling charges.	1		
			Total	

(Rupees

)

Special Terms and Conditions:

1. The firms are requested to visit the site and verify the 8.5 TR capacity ductable A/C which is kept open for inspection accordingly quote.
2. This rates quoted should be inclusive of all taxes.
3. Material supplied should confirm to ISI standards
4. The material should be supplied at the site as directed by the Engineer-in-Charge in good condition and nothing extra will be paid for transportation.
5. The work should be completed within 30 days after receipt of work order.

Yours faithfully,
For and on behalf of the Director General

(EXECUTIVE ENGINEER)